UNIVERSITY OF CALCUTTA

OFFICE OF THE UNIVERSITY ENGINEER
87/1, College Street
Darbhanga Building, GroundFloor
Kolkata-700073
Website :-www.caluniv.ac.in

NOTICE INVITING TENDER

University of Calcutta invites **sealed** tender from resourceful and bonafide contractors for the following work

1.	**N.I.T. No:**	**Eng /CT116/26-27 Dated:.30/10/2026**
2.	**Name of the work:**	**Urgent and Emergent plumbing and Sanitary works at the Toilets of Central Library through out the year of College street Campus under University of Calcutta**
3.	**Estimated Cost put to Tender:**	**88010.30(inclusive of taxes)**
4.	**Earnest Money:**	A sum of 2% of the estimated/quoted amount in the form of **CTS** demand draft in favour of University of Calcutta payable at Kolkata is to be attached with the Tender as earnest money failing which the tender will be treated cancelled. The earnest money will be returned to unsuccessful tenders on application after issuing of work order to the successful bidder. In case of successful tender the EMD will be returned on application after an equal amount of security deposit is ducted by the University from the running bills. **EMD is not exempted in any case.**
5.	**Time of completion:**	365 days
6.	Eligibility Criteria and Documents to be submitted along with Application.	Valid trade License , GST & PAN and credential for satisfactory completion of similar nature of job amounting75 % of the estimated value in a single tender in the last three financial years in Government /Government Undertaking or University of Calcutta.Original documents may be asked for verification of technical checking on the date of issuing tender paper . Failing to produce original documents, the tender will be rejected. The participant bidder must submit the following documents in sealed envelope in the tender box kept at the **Office of the Engineer at the Ground Floor of the Darbhanga Building, University of Calcutta, 87/1, College Street, Kolkata – 700073 within the last date of submission of the tender**. 1. NIT documents duly filled and signed by the intending bidder. 2. Bank Draft for EMD in favour of the University of Calcutta. 3. Self-attested copy of Valid trade License , GST & Pan and credentials for satisfactory completion of similar nature of jobs under Government, Government Undertaking and Universities etc. within last three years. 4. Application through postal service or courier service is not accepted.
7.	**Date of receipt of application for tender**	On 04/11/2026from 11 am to 4 pm (Must contain above mentioned. Documents. The application duly signed by Engineer CU should be enclosed with tender documents
8.	**Date of Sale/ issue of tender papers**	BE DOWNLOADED FROM WEBSITE. (www. caluniv.ac.in)
9.	**Date and Time of tender Submission**	**Dully filled and signed tender/quotation to be submitted ON 18/11/2026 from 11am to 2.00 PM in to the Tender Box kept in the Office of the University Engineer**
10.	**Date and Time of Tender Opening**	**ON ON 18/11/2026** after 3.00PM**at the Office of the University Engineer. Intending bidders are requested to be present at the time of opening tenders/quotations.**

N.B:

(i) N.I.T /NIQ no ,Name of work, name of the bidder and the date of opening tender/quotation should be written on the sealed envelope, failing which the tender/quotation will not be opened and thuscancelled.

(ii)The undersigned reserves the right to reject any or all Tenders/quotations without assigning any reason what soever.

UNIVERSITY ENGINEER (C.U)

UNIVERSITY OF CALCUTTA

Name of the work : Urgent and Emergent plumbing and Sanitary works at the Toilets of Central Library through out the year of College street Campus under University of Calcutta

N. I.T. no : Eng /CT116/26-27 Dated:.30/10/2026

Estimated cost Put to Tender:- 88010.30 (inclusive of all taxes)

Name of Agency:-

Address of Agency:-

Rate quoted by Agency:- …….. ……. …….. (in figure and words)

Signature of the Agency with date & stamp:-

UNIVERSITY OF CALCUTTA

N. I.T. no : Eng /CT116/26-27 Dated:.30/10/2026

Item Rate contract

GENERAL TERMS AND CONDITION

1. Eligible Tenders will have to download the tender papers from the website & drop the filled tender papers signed with seal and date at every page along with copy of Valid Trade license's, GST & PAN and Credential for satisfactory completion of similar nature of job amounting to at least seventy five percent of the job value in a single tender from any Government, Govt. undertaking or University of Calcutta in the last three financial yearin sealed envelope in the Tender box kept in the Office of the undersigned with in the specified time mentioned in the NITwhich will be opened by the undersigned or by his representative with in **the specified time and date mentioned in the NITThe tendered must write the name of the work , NIT no , the date of opening and name of the bidder on the envelop failing which the tender will not be opened thus will be treated as cancelled.**

2. The rate should be quoted after inspection of the site and inclusive of all incidental charges i.e. freight, insurances, labour insurances, handling charges, necessary government taxes, duties etc as well as the Water, Electricity charges which are to be paid as per rules .

3. The contractor shall be responsible to ensure compliance with the provision of minimum wages act 1948 as modified up to date and the rules made in respect of any employees, employed by the contractor directly or through the petty or subcontractor for the purpose of carrying this contract. The contractor shall be responsible for any damage, injury or loss caused by the work or workmen to any person, animal or material during the progress of work.

4. Liquidated damage will be charged to the contractor if they fail to complete the work within the stipulated time, 0.01% per day to a maximum limit of 10 % of the contract value .

5. The allotted time for completion of the work as specified in the NIT from the date of receipt of work order .Time is the essence of this contract. Normally no time extension will be granted. In case of prayer for extension of time the University authority has the full right reserved to grant it or discard it.

6. (a)If the successful contractor's bid rate is 80% or less than the estimated amount put to tender the contractor will have to submit a Bank Guarantee amounting to 10% of the Tendered amount before issue of Work order failing which the EMD will be forfeited and the agency may be blacklisted. The Bank Guarantee should be valid till the end of the contract period and shall be renewed accordingly if required. This bank Guarantee is an Additional Performance Security .So provision of deducting Security deposit from bills will hold goods per relevant clause of the contract. The bank Gurrantee shall be returned immediately on successful completion of contract.

(b) The University authority will retain a sum amounting to 10% of the bill of the contract for a period of six months from the date of completion of work as **Security Deposit**. Which will be released after a period of six months from the date of completion of the work on application.

7.A sum of 2% of the quoted amount in the form of CTS demand draft in favour of University of Calcutta payable at Kolkata is to be attached with the Tender as earnest money failing which the tender will be treated cancelled. The earnest money will be returned to unsuccessful tenders on application after issuing of work order to the successful bidder. In case of successful tender the EMD will be returned on application after an equal amount of security deposit is ducted by the University from the running bills. EMD is not exempted in any case.The earnest money will be returned to unsuccessful tenderers on application after issue of work order to the successful bidder for successful tenderer the EMD will be returned on application after an equal amount of security deposit is deducted from the running bills.

Amount:-Rs

D.D No..... Dated / /20

Name of Issuing Bank:--

Branch :-

8. Work is to be carried out as per specification laid in the B.O.Q or PWD specification as per instruction of the University Engineer or his representative.

9.The materials brought to site for execution of the work should by no means be taken out of site without the permission of the Engineer C.U.

10. The rates must be quoted in words in figure otherwise the tender will be cancelled.

11. The University will not be bound to accept the lowest bidder.

12.The University will not supply any materials to the contractor.

13. The contractor will work under the strict supervision of the Engineer/ Sub-Assistant Engineer. The estimate given along with the tender are provisional payment will be made on the actual work done jointly measured by the Engineer or his representative (Sub-Assistant- Engineer) & the contractor or his representative. The contractor will have to submit bill in printed format in duplicate.

14. The contractor will have to take necessary instruction from the Engineer CU/ Sub-Assistant Engineer regarding the execution of work.

15. Defect&liability Period:-The defect & liability periodwill be for a period of six months from the date of completion of the job. Any defects pointed out during this period has to be mend good by the agency at their own cost failing which the retention money will be forfeited.For AMC work the DLP period is restricted only upto the completion of work.

Sd/-

University Engineer

Name of the Agency:

Address :-

Signature of the Agency with date & stamp:-

N. I.T. no : Eng /CT116/26-27 Dated:.30/10/2026

BOQ for Urgent and Emergent plumbing and Sanitary works at the Toilets of Central Library through out the year of College street Campus under University of Calcutta

Sl.no	PWD SOR	Description of Items	unit	Rate	Quantity	Amount
1		Supplying, fitting and fixing G.I. pipes of TATA make with all necessary accessories, specials viz. socket, bend, tee, union, cross, elbo, nipple, longscrew, reducing socket, reducing tee, short piece etc. fitted with holder bats clamps, including cutting pipes, making threads, fitting, fixing etc. complete in all respect including cost of all necessary fittings as required,jointing materials and two coats of painting with approved paint in any position above ground. (Payment will be made on the centre line measurements of total pipe line including all specials. No separate payment will be made for accesories, specials. Payment for painting will be made seperately)				
		(A) For Exposed Work				
		(i) 15 mm dia. medium quality	Mtr	192	3	576
2		Supplying, fitting and fixing gunmetal wheel valve of approved brand and make tested to 21 kg per sq. cm. (for water lines only).				
		(ii) 15 mm dia	each	438	1	438
		(iii) 32 mm dia	each	1160	1	1160
		(iv) 40 mm dia	each	1590	1	1590
3		Supplying, fitting and fixing bib cock or stop cock.				
		(a) (i) Chromium plated Bib Cock short body (Equivalent to Code No. 511 & Model - Tropical / Sumthing Special of ESSCO or similar brand).	each	539	1	539
		(b) (i) Chromium plated Stop Cock (Equivalent to Code No. 513(A) & 513(B) & Model - Tropical / Sumthing Special of ESSCO or similar	each	493	1	493
		(e) PTMT (Polytetra Bib Cock / Stop Cock (Prayag or equivalent)	each	154	50	7700
		15 mm				

4		Supplying, fitting and fixing PVC pipes of approved make of Schedule 80 (medium duty) conforming to ASTMD - 1785 and threaded to match with GI Pipes as per IS : 1239 (Part - I). with all necessary accessories, specials viz. socket, bend, tee, union, cross, elbo, nipple, longscrew, reducing socket, reducing tee, short piece etc. fitted with holder bats clamps, including cutting pipes, making threads,fitting, fixing etc. complete in all respect including cost of all necessary fittings as required,jointing materials and two coats of painting with approved paint in any position above ground. (Payment will be made on the centre line measurements of total pipe line including all specials. No separate payment will be made for accesories, specials. Payment for painting will be made seperately)				
		(a) For Exposed Work				
		PVC Pipes				
		15 mm	metre	101	5	505
		20 mm	metre	129	5	645
5		Supplying, fitting and fixing 10 litre P.V.C. low-down cistern conforming to I.S. specification with P.V.C. fittings complete,C.I. brackets including two coats of painting to bracket etc.	each	1015	6	6090
6		Supplying, fitting and fixing low-down cistern parts.				
		(i) Internal fittings for cistern complete of approved make.	Each Set	284	15	4260
		ii) Outlet Assembly	each	279	15	4185
7		Supplying,fitting and fixing approved brand P.V.C. CONNECTOR white flexible, with both ends coupling with heavy brass C.P. nut, 15 mm dia.				
		(ii) 450 mm long	each	82	20	1640
8		Supplying,fitting and fixing approved brand 32 mm dia.P.V.C. waste pipe, with PVC coupling at one end fitted with necessary clamps.				
		(i) 600 mm long	each	43	20	860
9		Supplying, fitting and fixing E.W.C. in white glazed vitreous chinaware of approved make complete in position with necessary bolts, nuts etc.				
		(a) With 'P' trap/strap	each	1421	6	8526

10		Supplying, fitting and fixing Flat back urinal (half stall urinal) in white vitreous chinaware of approved make in position with brass screws on 75 mm X 75 mm X 75 mm wooden blocks complete.				
		(i) 635 mm X 395 mm X 420 mm	each	2869	0	0
		(ii) 470 mm X 280 mm X 340 mm	each	945	10	9450
11		Supplying, fitting and fixing Closet seat of approved make with lid and C.P. hinges, rubber buffer and brass screws complete.				
		(ii) Plastic (hallow type) white/BLACK	each	302	10	3020
12		Wash basin vitreous china of approved make (without fittings) supplied,fitted and fixed in position on 75mm X 75 mm X 75 mm wood blocks and C.I. brackets including two coats of painting of C.I. brackets				
		550 mm X 400 mm size	each	1155	4	4620
13		Supplying, fitting and fixing liquid soap container.	eACH	210.00	8.00	1680
14		Supplying,fitting and fixing approved brand 32 mm dia.P.V.C. waste pipe, with PVC coupling at one end fitted with necessary clamps.	Each	47.00	15.00	705
15		Supplying, fitting and fixing 18 mm thick marble partition slab with chawk doongri marbel square cut, both sides polished with two front corners rounded and edges polished.	Sqm	1426.00	3.00	4278
16		Supplying, fitting and fixing bevelled edged mirror 5.5 mm thick silver red as per I.S. 3438 / 1965 together with brass C.P. hinges.	EACH	484.00	5.00	2420
17		Dismantling and refixing marble or mosaic partition.	Each	100.00	5.00	500
18		Dismantling wash basin with brackets with or without waste fittings	Each	35.00	4.00	140

19		Dismantling E.P. or Anglo-Indian W.C.	Each	45.00	6.00	270
20		Dismantling and refixing marble or mosaic partition.	Each	100.00	5.00	500
21		Dismantling flush pipe of water closet.	Each	17.00	10.00	170
22		Dismantling urinal.	Each	33.00	10.00	330
23		Refixing urinal.	Each	35.00	5.00	175
25		Cleaning glazed tiles with acid.	SQM	10.00	80.00	800
26		Flush pointing to tiled floor in cement mortar (1:4) with admixture of pigment to match with colour of tiles including raking out joints	sQM	79.00	80.00	6320
A		**Total Tentative Basic cost**				**74585.00**
B		Goods & Service Tax onA@18%				**13425.30**
C		total Tentative cost+GST (A+B)				**88010.30**

Name of the Agency:

Address of the Agency:

Ratequoted by the Agency in words and figure:

Signature of the Agency with date and stamp.