

1st Corrigendum against the original e-tender vide ref no. DBT/Builder/AC/22-23 Dt: - 28.10.2022 and Tender ID: 2022 CU 418057 1

Subject : Corrigendum for B.O.Q.

Name of work: Supply, fitting, fixing & commissioning of the Air Conditioning machines in the DBT BUILDER facilities in Botany, Biochemistry and other participating departments in Ballygunge Science College Campus under the University of Calcutta.

All the bidders are requested to consider the following specifications and quantity for submitting bids in the e-tender portal. In this respect, the bid amount may be consider for the item nos. 1 /B to /F in addition with the serial no. 1 /A and the cumulative bid amount for 1/A to 1/F will be considered as final.

Sl.No.	Description of work	Unit	Quantity
1	Air conditioninning		
A)	SITC of 3star rating split air conditioner machine with R 32 gas incl.remote controller of folowing capacity suitable for operation on 230v +/- 10% volt ,50Hz,single phase ac supply with air cooled evaporator with copper coil fan & fan motor,air cooled condenser with copper coil,hermatically sealed rotary compressor,propeller fans,controls,control panels incl wiring,necy. power cable connection from unit to power socket,refrigerant pipe of appropriate size between indoor & outdoor unit upto 3 mtr length[both suction& delivery,incl gas charging complete as reqd, 1.5TR [Make: Hitachi/Daikin/Bluestar]	each	20
B)	Providing & fixing copper pipe thickness with nitrile rubber insulation not less than 0.6 mm& suitable size as required for supply& return refrigerant with suitable insulation for above Acs as per specification of manufacturer complete in all respect as required[in excess of 3.00 mtr length/Machine 1/4"[OD-6.35mm]	Rft	515
C)	Supplying & laying 20mm dia ISI marked PVC flexible pipe along with accessories on surface of the wall to drain out condensed water from indoor unit as required.	Rft	870
D)	S&F factory fabricatedM.S structure for resting/Placing of 1.5TR capacity split A.C outdoor unit on existing bldg. & fixed by MS fastner.	item	20
E)	S&F4C flexible copper cable of size 4sq.mm,from indoor to outdoor unit incl.connection,commissioning testing etc as reqd.[Polycab/Havells]	RM	450
F)	Hire & labour charges for shuttering with centering &necy. Staging upto 4mtr using approved stout props &thick hard wood planks of apprpd thickness with reqd.bracing for concrete slab,beams & coloumns,lintels curved or straight.....works (upto roof of G/F) When the height of a particular floor is more than 4mtr the equivalent flr height shall be taken as 4mtr 7 extra for works beyond the initial 4mtr shall be allowed under 12(e) for every 4mtr or part thereof.extra for staging beyond 4mtr in any floor.(H=12mtr,B=2mtr,L=1.5mtr) Vol=36cum	Cum	270

Sd/-
Prof. Binay Chaubey
H.O.D
Department of Botany
University of Calcutta